



CONTINUOUS FOOTING (WF) SCHEDULE 901-03

FOR CONSTRUCTION ABOVE FOOTING, SEE DETAILS. LONGITUDINAL REINFORCING. EQUAL SPACING U.N.O. TRANSVERSE REINFORCING

NOTE: 1. FOR DEPTH OF FOOTING, SEE G.S.N. U.N.O. 2. CENTER FOOTING ON CONSTRUCTION ABOVE U.N.O. 3. EXTEND FOOTINGS 12\"/>

MARK	DIMENSIONS		FOOTING REINFORCING	REMARKS
	HEIGHT	WIDTH		
WF1	12"	3'-0"	4 - #5 CONTINUOUS AND #4 AT 12" O.C. TRANSVERSE	---

SEE S5.3 FOR FOUNDATION PLAN NOTES:

1 - #5 CENTERED IN SOLID GROUTED CELL SPACED AT 24" O.C. - TYPICAL 16'-0" WALL. ALL WALLS TO BE SOLID GROUTED.

CONCRETE COLUMN WITH 5 - #8 VERTICAL REINFORCING WITH #3 TIES AT 8" O.C. TYPICAL. MIN DIA=16" MAX DIA=40" SEE ARCH'L FOR COLUMN PROFILE.

4" CONCRETE SLAB WITH #3 BARS AT 16" O.C. EACH WAY OVER 2" CLEAR SAND OVER 8 MIL, PUC VAPOR BARRIER - TYP U.N.O.

1 - #5 CENTERED IN SOLID GROUTED CELL SPACED AT 24" O.C. - TYPICAL 8'-0" WALL. ALL WALLS TO BE SOLID GROUTED.

SHADED AREA INDICATES DEPRESSED 4" CONCRETE SLAB WITH #3 BARS AT 16" O.C. EACH WAY OVER 2" CLEAR SAND OVER 8 MIL, PUC VAPOR BARRIER - TYP U.N.O.

1 - #5 CENTERED IN SOLID GROUTED CELL SPACED AT 24" O.C. - TYPICAL 16'-0" WALL. ALL WALLS TO BE SOLID GROUTED.

ISOLATED FOOTING (F) SCHEDULE 901-11

FOR CONSTRUCTION ABOVE FOOTING, SEE DETAILS. FOOTING REINFORCING. EQUAL SPACING U.N.O.

NOTE: 1. FOR DEPTH OF FOOTING, SEE G.S.N. U.N.O. 2. CENTER FOOTING ON CONSTRUCTION ABOVE U.N.O.

MARK	DIMENSIONS			FOOTING REINFORCING	HAIRPIN
	HEIGHT	WIDTH	LENGTH		
F1	12"	3'-0"	3'-0"	4 #5 EACH WAY	1 #6
F2	12"	4'-0"	4'-0"	5 #5 EACH WAY	1 #7
F3	12"	5'-0"	5'-0"	7 #5 EACH WAY	1 #8
F4	18"	7'-6"	7'-6"	9 #6 EACH WAY	1 #8

FOUNDATION PLAN
SCALE: 1/8" = 1'-0"

REVISIONS		SATISFACTORY TO:		SUBMITTED:		DEPARTMENT OF THE NAVY		PROJECT LOCATION		SPEC.	
NO.	DESCRIPTION	DATE	DATE	DATE	DATE	DATE	DATE	YUMA, ARIZONA	NAVFAC DRAWING NO.	NAVFAC DRAWING NO.	SHEET 49 OF
									8175782	8175782	

FINAL SUBMITTAL

S2.1